

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division,
ITEM NO:13
No.BBMP/EE/DD/Ten/09/2013-14, Date: 10.12.2013
SCHEDULE-B

NAME OF WORK: Improvements to Drain, Foot path 1st, 2nd, 3rd, 4th & 5th Cross
Brundavana Layout Mallasandra in Bagalagunte ward No 14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	239.25	90.0	Rupees Ninety Only
2	Removing B.S.Slab of drain and stacking etc., complete as per specifications.	Sqm	344.52	49.99	Rupees Forty Nine and Ninety Nine Paise Only
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	71.78	4200.0	Rupees Four Thousand Two Hundred Only
4	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	31.1	4600.0	Rupees Four Thousand Six Hundred Only
5	Refixing stone slabs of drains and pointing in CM 1:3 etc., complete as per specifications.	Sqm	344.52	65.0	Rupees Sixty Five Only
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete as per specifications.	Sqm	229.68	340.03	Rupees Three Hundred Forty and Three Paise Only
7	Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	510.4	900.0	Rupees Nine Hundred Only

P. Dasarahalli
Signature of the Contractor

[Signature]
Executive Engineer

8	Supplying and fixing precast reinforced concrete slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. complete as per specifications.	Sqm	574.2	1592.74	Rupees One Thousand Five Hundred Ninety Two and Seventy Four Paise Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specifications.	Cum	239.25	70.0	Rupees Seventy Only



Signature of the Contractor


Executive Engineer,
Dasarahalli Division,